

THIS DRAWING AND ALL INFORMATION CONTAINED HEREIN IS THE EXCLUSIVE PROPERTY OF FISHER AND ASSOCIATES, ARCHITECTS PLANNERS INTERIOR DESIGNERS AND SHALL NOT BE REPRODUCED, COPIED, OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM, WITHOUT THE WRITTEN PERMISSION OF FISHER AND ASSOCIATES, ARCHITECTS PLANNERS INTERIOR DESIGNERS. THIS DRAWING IS NOT FOR GENERAL USE OR PUBLICATION. ALL RIGHTS RESERVED.
 TO THE BEST OF MY KNOWLEDGE, THE SPECIFICATIONS AND PLANS SHOWN HEREIN COMPLY WITH THE APPLICABLE MINIMUM BUILDING CODES IN EFFECT AT THIS TIME.

FISHER AND ASSOCIATES, LLC.
 ARCHITECTS
 PLANNERS
 INTERIOR DESIGNERS
 AA 26001738
 2315 BELLEAIR RD. CLEARWATER, FL 33764 (727) 443-4456

FOUNDATION PLAN
RETAIL BUILDING AT WINTER GARDEN
MARSH ROAD AT CR 545 (AVALON RD)
WINTER GARDEN, FL 34787


RELEASED FOR:	
BID	12.11.23
PERMIT	12.08.23
CONSTR.	

REVISIONS:	
12.08.23	SBUX/REV

DIMITRIOS MELANDINOS
 PE # 0060182

S11

Issue Date: 03.31.23
 Project No.: 23-136



FOUNDATION PLAN
 SCALE: 1/8" = 1'-0"


NOTE: SEE ARCH. DWGS. FOR LOCATION OF MASONRY CONTROL JOINTS. SEE 3/S4.1. LOCATE C.J. AT 34'-0" O.C. (MAX.) AND 2'-0" (MIN.) FROM DOOR OR WINDOW EDGE.
 SEE ARCH DWGS. FOR LOCATION OF SPLIT FACE MASONRY.

MASONRY WALL REINFORCEMENT SCHEDULE
 (SEE 6/S4.1)
 WALLS ARE TO BE REINFORCED AS SHOWN BELOW. IN ADDITION VERT. BARS SHALL BE PLACED @ CORNERS, EACH SIDE OF OPENINGS AND INTERSECTIONS. DOWEL INTO FOOTINGS AND TIE BEAMS. HORIZONTAL REINFORCEMENT = 3 GA. @ 16" O.C.
 NOTE: FILL ALL CELLS SOLID BELOW FINISH FLOOR.
 8" CMU WALL w/ 1/2" VERTICAL BARS AT 24" O.C. (NOTE: PROVIDE SAME WALL REINF. ABOVE OPENINGS)
 8" CMU WALL w/ 1/2" VERTICAL BARS AT 8" O.C. (EXTEND VERTICAL BARS UP TO T.O. MAB.)

MARK	SIZE	THK	REINF. EA. WAY	COMMENTS
WF2.0	2'-0" x CONT.	1'-0"	(3) #5 CONT. (BOT.)	
WF3.0	3'-0" x CONT.	1'-0"	(4) #5 CONT. (BOT.)	
F4.0	4'-0" x 4'-0"	1'-0"	(5) #5 (BOT.)	
F4.1	4'-0" x 4'-0"	2'-0"	(5) #5 (BOT.)	
F5.0	5'-0" x 5'-0"	1'-0"	(6) #5 (BOT.)	
F6.0	6'-0" x 6'-0"	1'-4"	(7) #5 (BOT.)	

FOUNDATION PLAN NOTES

- SLAB ON GRADE TO BE 4" THICK w/ 6 x 6 - W14 x W14 W/F ON VAPOR BARRIER AND COMPACTED FILL (UN.O.)
- TOP OF SLAB = 0'-0" (UN.O.)
- DIMENSIONS ARE TO FACE OF MASONRY AND CENTERLINE OF COLUMNS.
- CENTER FOOTINGS UNDER CMU WALLS AND COLUMNS.
- SEE MASONRY LEGEND FOR WALL REINFORCEMENT.
- SEE ARCH. DWGS. FOR VENEER.
- TOP OF FOOTING ELEVATION = -1'-4" (UN.O.)
- SEE ARCH. DWGS. FOR SIZE AND LOCATION OF MASONRY OPENINGS (N.O.)
- STEP FOOTING TO MAINTAIN 1'-0" COVERAGE. (SEE 8/S4.1) SEE CIVIL DWGS. FOR FINISH GRADE
- PROVIDE 2'-6" x 2'-6" FOUNDATION CORNER BARS AT ALL CORNERS AND INTERSECTIONS (MATCH REINF. BARS)



CONCRETE COLUMN SCHEDULE
 (SEE 10/S4.1 & 11/S4.1)

THIS DRAWING AND ALL INFORMATION CONTAINED HEREIN IS THE EXCLUSIVE PROPERTY OF FISHER AND ASSOCIATES, LLC. IT IS NOT TO BE COPIED OR USED IN ANY MANNER WITHOUT THE WRITTEN PERMISSION OF FISHER AND ASSOCIATES, LLC. NO PART OF THIS DRAWING IS TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM, WITHOUT THE WRITTEN PERMISSION OF FISHER AND ASSOCIATES, LLC. ALL RIGHTS RESERVED.
 TO THE BEST OF MY KNOWLEDGE, THE SPECIFICATIONS AND PLANS SHOWN HEREIN COMPLY WITH THE APPLICABLE MINIMUM BUILDING CODES IN EFFECT AT THIS TIME.

FISHER AND ASSOCIATES, LLC.
 ARCHITECTS
 PLANNERS
 INTERIOR DESIGNERS
 AA 26001738
 2315 BELLEAIR RD. CLEARWATER, FL 33764 (727) 443-4456

ROOF FRAMING PLAN
RETAIL BUILDING AT WINTER GARDEN
MARSH ROAD AT CR 545 (AVALON RD)
WINTER GARDEN, FL 34787

RELEASED FOR:

BID	12.11.23
PERMIT	12.08.23
CONSTR.	


REVISIONS:

Δ	12.08.23	SBUX/REV

DIMITRIOS MELANDINOS
 PE # 0060182


S2.1

Issue Date: 03.31.23
 Project No.: 23-136



TIE BEAM SCHEDULE
 (SEE 6/84.1 & 11/84.1)

MARK	WIDTH	DEPTH	TOP REINF.	MID. REINF.	BOT. REINF.	STIRRUPS	TYPE	COMMENTS
TB-1	8"	16"	(2) #5	--	(2) #5	--	A	
TB-2	8"	24"	(2) #5	(2) #5	(2) #5	--	B	
TB-3	8"	32"	(2) #5	(4) #5	(2) #5	--	C	
CB-1	8"	15' 5/8"	(2) #6	-	(2) #6	#3 AT 6" O.C.	D	
CB-2	8"	31' 5/8"	(4) #6	-	(4) #6	#3 AT 12" O.C.	E	



ROOF FRAMING PLAN
 SCALE: 1/4" = 1'-0"

- ROOF FRAMING NOTES**
- RN-1 SLOPE ROOF DOWN IN THIS DIRECTION AT 1/4" PER FOOT
 - RN-2 INDICATES DIAGONAL BRIDGING AT END BAYS AS SHOWN
 - RN-3 INDICATES CONT. HORIZ. BRIDGING AS SHOWN
 - RN-4 INDICATES PRE-ENGINEERED ALUM. AWNING / CANTILEVERED CANOPY (SEE ARCH.)
 - RN-5 TB-2, BOT. / BM. = 14'-0"
 - RN-6 TB-1, BOT. / BM. = 14'-8"
 - RN-7 TB-1, BOT. / BM. VARIES (STEP AS REQ. SEE 2/84.3)
 - RN-8 TB-2, BOT. / BM. = 15'-4"
 - RN-9 TB-1, BOT. / BM. VARIES (STEP AS REQ. SEE 2/84.3)
 - RN-10 TB-3, BOT. / BM. = 13'-4"
 - RN-11 TB-1, BOT. / BM. = 15'-4"
 - RN-12 TB-1, BOT. / BM. = 14'-0"
 - RN-13 INDICATES L 4 x 4 x 3/8 ANGLE BRACE FOR PARAPET AT EACH JOIST OR AS SHOWN ON PLAN (SEE 8/3.1 & 8/3.2)
 - RN-14 INDICATES L 4 x 4 x 3/8 ANGLE BRACE FOR STOREFRONT AT EACH JOIST OR AS SHOWN ON PLAN (SEE 2/83.2)

TOP OF MASONRY LEGEND
 (SEE 6/84.1 FOR TYPICAL TIE BEAM CONN.)

---	T.O. MAS. = 15'-4" (JST BRG)
----	T.O. MAS. = 21'-4"
-----	T.O. MAS. = 22'-8"
-----	T.O. MAS. = 25'-8"

- ROOF FRAMING PLAN NOTES**
- ROOF UPLIFT PLAN - SEE 8/3.1
 - SEE FOUNDATION PLAN FOR DIMENSIONS.
 - SEE CMU LEGEND FOR TOP OF MASONRY ELEVATIONS.
 - COORDINATE ALL DIMENSIONS WITH ARCHITECTURAL DRAWINGS.
 - DECK TO BE GALV. 18 GA. TYPE "B" METAL DECK 3 SPAN MIN. FASTENING = AT EA. SUPPORT: (1) 5/8" Φ PUDDLE WELDS PER 36" AND BETWEEN EACH SUPPORT INSTALL (1) #0 TEK SCREWS AT SIDELAP. WELD DECK TO CONTINUOUS DECK ANGLE W/ 5/8" Φ PUDDLE WELDS AT 6" O.C.
 - SEE CONC. BEAM / TIE BEAM SCHEDULE ON 8/2.1
 - PROVIDE 2'-6" x 2'-6" TIE BEAM CORNER BARS AT ALL CORNERS AND INTERSECTIONS. (MATCH REINF. BARS)
 - COORDINATE SIZE, WEIGHT, AND LOCATION OF ROOF TOP UNITS WITH MECHANICAL DRAWINGS (SEE 1/84.2, 2/84.2, & 3/84.2)

LINTEL SCHEDULE
 MINIMUM BEARING = 8"

L-1	PRECAST LINTEL w/ (1) #5 CONT. FULLY GROUTED
L-2	POWERS STEEL LINTEL (F58-8") AND (1) K.O. BLK. w/ (1) #5 CONT.
L-3	PRECAST LINTEL w/ (1) #5 CONT. FULLY GROUTED AND (2) K.O. BLK. w/ (1) #5 CONT. AND (1) 4" BLK.

METAL STUDS FASTENING NOTES
(UNO.)

1. METAL STUDS SHALL BE CONNECTED TO STRUCTURAL STEEL w/ (2) $\emptyset 11"$ Φ P.D.F.'s
2. METAL STUDS SHALL BE CONNECTED TO METAL STUDS / CLIP ANGLES w/ MIN. (4) NO. 12-14 SCREWS
3. CONTINUOUS TRACK SHALL BE CONNECTED TO STRUCTURAL STEEL w/ (2) $\emptyset 11"$ Φ P.D.F.'s AT 24" O.C.
4. CONTINUOUS TRACK / STUDS SHALL BE CONNECTED TO CMU w/ (2) 1/4" Φ TAPCONS AT 24" O.C.
5. CONNECT SHEATHING TO METAL STUDS w/ NO. 12-14 SCREWS AT 6" O.C.
6. 14 GA. CLIP ANGLES SHALL BE CONNECTED TO CMU w/ (2) 1/4" Φ TAPCONS

MTL. STD WELDING NOTE:

WELD TRUSS w/ 3/32" OR 1/8" AUG TYPE $\emptyset 13$ OR 1/2" ROD WITH A WELDING HEAT OF 60-110 AMPERES DEPENDING ON GAGE OF MATERIAL AND FIT

COORDINATE ALL SOFFIT HEIGHTS AND SECTIONS w/ ARCH

COORDINATE ALL DIMENSIONS WITH ARCHITECTURAL DRAWINGS

SEE ARCH FOR SHEATHING




3300 Henderson Blvd., Suite 202, Tampa, FL 33609
P. (813) 835-5311

Structural Engineers
Dimitrios Melandinos
PE: 52167 C-4886

THIS DRAWING AND ALL INFORMATION CONTAINED HEREIN IS THE EXCLUSIVE PROPERTY OF FISHER AND ASSOCIATES, LLC. IT IS NOT TO BE COPIED OR USED IN ANY MANNER WITHOUT THE WRITTEN PERMISSION OF FISHER AND ASSOCIATES, LLC. NO PART OF THIS DRAWING IS TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM, WITHOUT THE WRITTEN PERMISSION OF FISHER AND ASSOCIATES, LLC. THIS DRAWING IS NOT FOR GENERAL USE OR PUBLICATION. ALL RIGHTS RESERVED.
TO THE BEST OF MY KNOWLEDGE, THE SPECIFICATIONS AND PLANS SHOWN HEREIN COMPLY WITH THE APPLICABLE MINIMUM BUILDING CODES IN EFFECT AT THIS TIME.

FISHER AND ASSOCIATES, LLC.

ARCHITECTS
PLANNERS
INTERIOR DESIGNERS



AA 26001738
2315 BELLEAIR RD. CLEARWATER, FL 33764 (727) 443-4456

WALL SECTIONS
RETAIL BUILDING AT WINTER GARDEN
MARSH ROAD AT CR 545 (AVALON RD)
WINTER GARDEN, FL 34787

RELEASED FOR:

BID 12.11.23

PERMIT 12.08.23

CONSTR.

REVISIONS:


NO.	DESCRIPTION

DIMITRIOS MELANDINOS
PE # 0060182


S3.1

Issue Date: 03.31.23


Project No.: 23-136



1 SECTION
SCALE: 1/2" = 1'-0"



2 SECTION
SCALE: 1/2" = 1'-0"



3 SECTION
SCALE: 1/2" = 1'-0"

METAL STUDS FASTENING NOTES
(UNO.)

1. METAL STUDS SHALL BE CONNECTED TO STRUCTURAL STEEL w/ (2) Ø1/11" ϕ P.D.F.'s
2. METAL STUDS SHALL BE CONNECTED TO METAL STUDS / CLIP ANGLES w/ MIN. (4) NO. 12-14 SCREWS
3. CONTINUOUS TRACK SHALL BE CONNECTED TO STRUCTURAL STEEL w/ (2) Ø1/11" ϕ P.D.F.'s AT 24" O.C.
4. CONTINUOUS TRACK / STUDS SHALL BE CONNECTED TO CMU w/ (2) 1/4" ϕ TAPCONS AT 24" O.C.
5. CONNECT SHEATHING TO METAL STUDS w/ NO. 12-14 SCREWS AT 6" O.C.
6. 14 GA. CLIP ANGLES SHALL BE CONNECTED TO CMU w/ (2) 1/4" ϕ TAPCONS

MTL. STD WELDING NOTE:

WELD TRUSS w/ 3/32" OR 1/8" AUG TYPE Ø013 OR 1/2" ROD WITH A WELDING HEAT OF 60-110 AMPERES DEPENDING ON GAGE OF MATERIAL AND FIT


COORDINATE ALL SOFFIT HEIGHTS AND SECTIONS w/ ARCH

COORDINATE ALL DIMENSIONS WITH ARCHITECTURAL DRAWINGS


SEE ARCH FOR SHEATHING

CENTER FOR INNOVATIVE STRUCTURES
3300 Henderson Blvd., Suite 202, Tampa, FL 33609
P: (813) 835-5311
Structural Engineers
Dimitrios Melandinos
PE: 52167 C-4886


THIS DRAWING AND ALL INFORMATION CONTAINED HEREIN IS THE EXCLUSIVE PROPERTY OF FISHER AND ASSOCIATES, LLC. IT IS NOT TO BE COPIED OR USED IN ANY MANNER WITHOUT THE WRITTEN PERMISSION OF FISHER AND ASSOCIATES, LLC. NO PART OF THIS DRAWING IS TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM, WITHOUT THE WRITTEN PERMISSION OF FISHER AND ASSOCIATES, LLC. THIS DRAWING IS NOT FOR GENERAL USE OR PUBLICATION. ALL RIGHTS RESERVED.
TO THE BEST OF MY KNOWLEDGE, THE SPECIFICATIONS AND PLANS SHOWN HEREIN COMPLY WITH THE APPLICABLE MINIMUM BUILDING CODES IN EFFECT AT THIS TIME.



1 SECTION
SCALE: 1/2" = 1'-0"



2 SECTION
SCALE: 1/2" = 1'-0"



3 SECTION
SCALE: 1/2" = 1'-0"

FISHER AND ASSOCIATES, LLC.

ARCHITECTS
PLANNERS
INTERIOR DESIGNERS
AA 26001738
2315 BELLEAIR RD. CLEARWATER, FL 33764 (727) 443-4456

RELEASED FOR:

BID	12.11.23
PERMIT	12.08.23
CONSTR.	

REVISIONS:

Δ	12.08.23	SBUX/REV

DIMITRIOS MELANDINOS
PE # 0060182

S3.2

Issue Date: 03.31.23
Project No.: 23-136

THIS DRAWING AND ALL INFORMATION CONTAINED HEREIN IS THE EXCLUSIVE PROPERTY OF FISHER AND ASSOCIATES, LLC. IT IS NOT TO BE COPIED OR USED IN ANY MANNER WITHOUT THE WRITTEN PERMISSION OF FISHER AND ASSOCIATES, LLC. PERMISSION WILL BE GRANTED UPON REQUEST. THIS DRAWING IS NOT FOR GENERAL USE OR PUBLICATION. ALL RIGHTS RESERVED.
 TO THE BEST OF MY KNOWLEDGE, THE SPECIFICATIONS AND PLANS SHOWN HEREIN COMPLY WITH THE APPLICABLE MINIMUM BUILDING CODES IN EFFECT AT THIS TIME.

FISHER AND ASSOCIATES, LLC.
 ARCHITECTS
 PLANNERS
 INTERIOR DESIGNERS
 AA 26001738
 2315 BELLEAIR RD. CLEARWATER, FL 33764 (727) 443-4456

DETAILS
RETAIL BUILDING AT WINTER GARDEN
MARSH ROAD AT CR 545 (AVALON RD)
WINTER GARDEN, FL 34787














RELEASED FOR:	
BID	12.11.23
PERMIT	12.08.23
CONSTR.	

REVISIONS:	

DIMITRIOS MELANDINOS
 PE # 0060182

S4.1

Issue Date: 03.31.23
 Project No.: 23-136



THIS DRAWING AND ALL INFORMATION CONTAINED HEREIN IS THE EXCLUSIVE PROPERTY OF FISHER AND ASSOCIATES, LLC. IT IS NOT TO BE COPIED OR USED IN ANY MANNER WITHOUT THE WRITTEN PERMISSION OF FISHER AND ASSOCIATES, LLC. THIS DRAWING IS NOT FOR GENERAL USE OR PUBLICATION. ALL RIGHTS RESERVED.
 TO THE BEST OF MY KNOWLEDGE, THE SPECIFICATIONS AND PLANS SHOWN HEREIN COMPLY WITH THE APPLICABLE MINIMUM BUILDING CODES IN EFFECT AT THIS TIME.

FISHER AND ASSOCIATES, LLC.
 ARCHITECTS
 PLANNERS
 INTERIOR DESIGNERS
 AA 26001738
 2315 BELLEAIR RD. CLEARWATER, FL 34764 (727) 443-4456

DETAILS
RETAIL BUILDING AT WINTER GARDEN
 MARSH ROAD AT CR 545 (AVALON RD)
 WINTER GARDEN, FL 34787

RELEASED FOR:

BID	12.11.23
PERMIT	12.08.23
CONSTR.	













REVISIONS:

NO.	DESCRIPTION

DIMITRIOS MELANDINOS
 PE # 0060182

S4.2

Issue Date: 03.31.23
 Project No.: 23-136



THIS DRAWING AND ALL INFORMATION CONTAINED HEREIN IS THE EXCLUSIVE PROPERTY OF FISHER AND ASSOCIATES, LLC. IT IS NOT TO BE COPIED OR USED IN ANY MANNER WITHOUT THE WRITTEN PERMISSION OF FISHER AND ASSOCIATES, LLC. THIS DRAWING IS NOT FOR GENERAL USE OR PUBLICATION. ALL RIGHTS ARE RESERVED.
 TO THE BEST OF MY KNOWLEDGE, THE SPECIFICATIONS AND PLANS SHOWN HEREIN COMPLY WITH THE APPLICABLE MINIMUM BUILDING CODES IN EFFECT AT THIS TIME.

FISHER AND ASSOCIATES, LLC.
 ARCHITECTS
 PLANNERS
 INTERIOR DESIGNERS
 AA 26001738
 2315 BELLEAIR RD. CLEARWATER, FL 33764 (727) 443-4456

DETAILS
RETAIL BUILDING AT WINTER GARDEN
 MARSH ROAD AT CR 545 (AVALON RD)
 WINTER GARDEN, FL 34787

RELEASED FOR:

BID	12.11.23
PERMIT	12.08.23
CONSTR.	









REVISIONS:

Δ	12.08.23	SBUX/REV

DIMITRIOS MELANDINOS
 PE # 0060182

S4.3

Issue Date: 03.31.23
 Project No.: 23-136



THIS DRAWING AND ALL INFORMATION CONTAINED HEREIN IS THE EXCLUSIVE PROPERTY OF FISHER AND ASSOCIATES, AND IS NOT TO BE COPIED OR USED IN ANY MANNER WITHOUT THE WRITTEN PERMISSION OF FISHER AND ASSOCIATES. THIS DRAWING IS NOT FOR GENERAL USE OR PUBLICATION. ALL RIGHTS ARE RESERVED.
TO THE BEST OF MY KNOWLEDGE, THE SPECIFICATIONS AND PLANS SHOWN HEREIN COMPLY WITH THE APPLICABLE MINIMUM BUILDING CODES IN EFFECT AT THIS TIME.

FISHER AND ASSOCIATES, LLC.
ARCHITECTS
PLANNERS
INTERIOR DESIGNERS
AA 26001738
2315 BELLEAIR RD. CLEARWATER, FL 33764 (727) 443-4436

GENERAL NOTES
RETAIL BUILDING AT WINTER GARDEN
MARSH ROAD AT CR 545 (AVALON RD)
WINTER GARDEN, FL 34787


RELEASED FOR:	
BID	12.11.23
PERMIT	12.08.23
CONSTR.	

REVISIONS:	

DIMITRIOS MELANDINOS
PE # 0060182

S5.1

Issue Date: 03.31.23
Project No.: 23-136




ROOF UPLIFT PLAN (PSF) - ULTIMATE

TRIB. AREA (FT ²)	ZONE 1'	ZONE 1	ZONE 2	ZONE 3
	INTERIOR	PERIMETER	PERIMETER	CORNERS
10	39.6	69.0	91.0	124.0
20	39.6	65.3	85.5	113.0
50	39.6	58.0	76.3	96.5
100	39.6	54.3	72.6	85.5
200	34.1	50.6	65.3	72.6
500	26.8	43.3	58.0	58.0
1000	21.3	43.3	58.0	58.0

0.2h = 4 ft
0.6h = 10 ft
h = MEAN ROOF HEIGHT

NOTE: STL. JOIST MANUFACTURER MAY REDUCE UPLIFT LOADS BY 5 PSF FOR UPLIFT DESIGN



WALL PRESSURES (PSF) - ULTIMATE

TRIB. AREA (FT ²)	ZONE 4 (+)	ZONE 4 (-)	ZONE 5 (+)	ZONE 5 (-)
	10	43.3	46.9	43.3
20	41.4	45.1	41.4	54.3
50	39.6	43.3	39.6	48.8
100	36.7	40.7	36.7	46.9
200	35.2	39.6	35.2	41.4
500	32.3	35.9	32.3	35.9

a = 7 ft

STRUCTURAL NOTES

- DESIGN CRITERIA**
- Building Code: Florida Building Code, 7th edition (2020), ASCE 7-16.
 - Design Live Load:
 - Roof = 20 PSF (trib area = 0 - 200 SF)
 - per Code (trib area = 201 - 600 SF)
 - 12 PSF (trib area = > 600 SF)
 - Design Dead Loads:
 - Roof = 20 PSF
 - Ultimate Design Wind Speed = 139 MPH
Nominal Design Wind Speed = 108 MPH
 - Risk Category II
 - Wind Exposure Category = C.
 - Internal Pressure (G_{Cp}) = (+/-) 0.18 - Enclosed.
 - Other Loads: Contractor shall submit loading information for all equipment not shown on the drawings, or differing from those shown on the drawings.
- MISCELLANEOUS**
- The Contractor is responsible for the means and methods of the construction of the contents of these documents. This shall include, but is not limited to, temporary bracing, shoring, tie downs and other provisions which will ensure the safety at the jobsite until the entire structural system has been installed.
 - Do not scale these drawings. Coordinate all dimensions, elevations and openings with the architectural drawings and all other trades. Report to this office any discrepancies or omissions found in the contract document.
 - The general contractor shall coordinate all aspects of all drawings prior to fabrication of any structural components and final bidding.
- SUBMITTALS**
- All shop drawings shall be submitted and approved prior to construction. Allow (10) working days for approval from this office. Drawings / submittals shall be signed and sealed by a Florida licensed engineer.
 - Poured in Place Concrete:
 - Proposed concrete mix design in accordance with ACI 301 Chapter 3, and location.
 - Detailed shop drawings of reinforcing bars showing number, size, and location.
 - Formwork and shoring drawings as required by the Florida Threshold Law.
 - Concrete Masonry Units:
 - Detailed shop drawings of reinforcing bars showing number, size, and location.
 - Type of units and compression test results.
 - Structural Steel: Detailed shop drawings showing all member sizes, welds, bolts, connection details, layout, etc., as required to fabricate and erect the steel framing.
 - Joists and Girders: Detailed shop drawings showing joists, joist girders, bridging, accessories and connections. Calculations signed and sealed by a licensed Florida engineer.
 - Metal Deck: Detailed shop drawings showing layout, type, fastening and all accessory materials.
 - Cold Formed Steel: Detailed drawings showing layout, size, gauge, bracing, fastening and all accessory materials.

- SITE WORK**
- The design soil bearing pressure = 3,000 PSF
 - A soil investigation has been completed by Terracon Consultants, Inc., project # H1215368, dated December 8, 2022. All site preparation shall be done in accordance with this document.
 - Notify the soils engineer if the footing excavation reveals materials or conditions not anticipated in the soil's report.
 - A testing laboratory shall be retained to perform all the tests outlined in the soil's report.
 - Foundation walls that retain soil shall be braced until floors slabs are in place.

- CONCRETE MASONRY UNITS**
- Blocks shall be normal weight Grade N hollow load bearing masonry units which conform to ASTM C90.
 - Net compressive test strength of units = 2000 PSI
 - f_m = 2000 PSI
 - Mortar shall be type M or S and conform to ASTM C270.
 - Fill all cells containing reinforcing with coarse grout.
 - Coarse grout shall conform to ASTM C476
 - 3000 PSI at 28 days
 - 3/8" aggregate
 - 8"-10" slump
 - All work shall conform to TMS 602.
 - Reinforcing bars shall be lapped 48 diameters where spliced.
 - All vertical bars shall be held in position at the top and bottom and with a minimum clearance of 1/4" to the masonry walls and one diameter between bars.
 - Horizontal reinforcing shall conform to ASTM A82.
 - Horizontal reinforcing shall be 9 gauge (U.N.O.) ladder type Dur-o-wall (or equal) at 16" o.c. and shall be lapped a minimum of 6" at splices.
 - Store masonry on pallets and cover with visqueen.
 - Masonry shall be placed in running bond with 3/8" face shell bedding mortar joints, vertical and horizontal.
 - Grouting options
 - 4" high lifts with no observation holes.
 - 8" high lifts with observation holes. Observation holes shall be 4" x 4" sawcuts at the base course of all reinforcing.
 - Space masonry control joints at a maximum of 34'-0" o.c. (U.N.O.).
 - Masonry inspection shall be provided per TMS 402.
 - Provide a 8" x 8" reinforced precast lintels at all openings less than 8'-0" o.c. (U.N.O.) with a minimum end bearing = 8".

- STEEL BAR JOIST AND JOIST GIRDERS**
- Codes and Standards:
 - AISC Standard Specifications for Open Web Steel Joists
 - AISC Standard Specifications for Joist Girders
 - The Recommended Code of Standard Practice for Steel Joists and Joist Girder
 - The Steel Joist Institute
 - Steel joist manufacturer shall be a member of The Steel Joist Institute.
 - See Standard Joist Specifications for camber requirements.
 - Verify weight and location of all equipment or unique loads with contractor prior to fabrication of joists.
 - Design roof joists and bridging for the net uplift as shown on plans per Standard Joist Institute.
 - Joists, girders and accessories shall have one shop coat of paint. See architectural drawings for preferred color.
 - Joists shall bear a minimum of 4" on masonry and 2 1/2" on steel (UNO).
 - Provide bottom chord ceiling extensions where required by architect.
 - The joist bridging shall be properly installed before construction loads are applied.
 - Joist design engineer shall be provided with a copy of these documents.

- ROOF DECK**
- Metal roof deck shall conform to the specifications of The Steel Deck Institute.
 - Metal roof deck shall be 1 1/2" deep, wide rib Type B and galvanized. See plan for gauge.
 - Install all decking (3) span continuous.
 - Use weld washers for decking 24 gauge and thinner.
 - End bearing shall be 1 1/2" minimum.
 - End joints shall be lapped 2" minimum.
 - See plan for fastening requirements, all welds shall be cleaned and painted.


- EPOXY ADHESIVE**
- Masonry: HILTI HIT-HY 270 or approved equal
 - Concrete: HILTI HIT-HY 200 or approved equal

- GROUT - STRUCTURAL STEEL**
- Nonmetallic, Shrinkage-Resistant Grout: Premixed, nonmetallic, noncorrosive, nonstaining grout containing selected silica sands, portland cement, shrinkage compensating agents, plasticizing and water-reducing agents, complying with ASTM C1107, "Standard Specification for Packaged Dry, Hydraulic-Cement Grout (Nonshrink)," of consistency suitable for application, and a 30-minute working time. Minimum 6000 psi compressive strength.
- Provide one of the following products:
- "Euro N-S Grout;" Euclid Chemical Co.
 - "Vibropruf #11;" Lambert Corp.
 - "Crystex;" L & M Construction Chemicals, Inc.
 - "Masterflow 928 and 713;" Master Builders Technologies, Inc.
 - "Sonogrot 14;" Sonneborn Building Product - ChemRex, Inc.


- POURED-IN-PLACED CONCRETE**
- Codes and Standards:
 - ACI 318 "Building Code Requirements for Reinforced Concrete"
 - ACI 315 "Details and Detailing of Concrete Reinforcement"
 - ACI 301 "Specifications for Structural Concrete for Buildings"
 - Concrete is to be normal weight conforming to ASTM C94:
 - Portland Cement - ASTM C150, Type I
 - Aggregates (3/4" maximum) - ASTM C33
 - Air entraining - ASTM C260
 - Water Reducing - ASTM C494
 - Flyash (20% maximum) - Class F ASTM C618
 - Water - Potable
 - Slump Range - 3" - 5"
 - Placement Time (Maximum) - 90 minutes from batch time
 - Minimum compressive strength after 28 days:
 - Footings, slab on form deck, masonry fill - 3000 PSI
 - Columns, beams, walls - 4000 PSI
 - Reinforcing steel is to be Grade 60 conforming to ASTM A615
 - Minimum lap splice as follows:

BAR SIZE	f _c	Splice Length
#6 & SMALLER	3000 psi	58 BAR Diameters
#6 & SMALLER	4000 psi	50 BAR Diameters
#7 & LARGER	3000 psi	72 BAR Diameters
#7 & LARGER	4000 psi	63 BAR Diameters
 - Minimum bar cover:
 - Footings, retaining wall - 3"
 - Columns, beams, slabs - 1 1/2"
 - Provide corner bars which match the horizontal bars at all wall footings and tie beams.
 - Welding reinforcing if required shall conform to AWS D1.4.
 - Slab-on-Grade: Installation shall conform to ACI 302.1R:
 - Welded wire fabric - ASTM A185, ASTM A497; lap mesh 6" minimum at joints.
 - Moisture barrier - 6 mil polyethylene
 - Compressive strength - 4000 PSI
 - Sawcut joints and construction joints shall be cleaned and filled with epoxy filler as required by owner.
 - Contractor shall have a thorough understanding of the owner's expectation of the slab-on-grade (cracks, levelness, etc.) and shall provide adequate equipment, labor and materials (including water-reducing agents, installation and curing procedures, etc.) to assure a slab that will be acceptable to the owner.
 - Contractor shall replace or repair (at his cost) any portion of the slab that is not acceptable to the owner.
 - Install ties, spacers, chairs, etc. (per CRSI recommendations) necessary to securely hold reinforcing during concrete placement. Use plastic tips at all exposed surfaces.
 - Use internal vibrators to consolidate all concrete.
 - Concrete curing options
 - Liquid membrane forming chemical compound conforming to ASTM C509.
 - Continuous moisture in accordance with ACI 301.
 - Concrete shall be finished per architectural drawings.
 - A testing laboratory shall perform the following concrete tests for each 50 cubic yards. Send test results to the owner, architect, structural engineer and General Contractor.
 - Slump test - ASTM C143
 - Four cylinder strength test - ASTM C39: test one cylinder after 7 days, test two after 28 days and hold one in reserve.
 - All beams shall be poured monolithically.
 - Exposed edges of columns and beams shall be chamfered 3/4" unless noted otherwise on architectural drawings.
 - Coat all forms with a commercial compound that will not bond or adversely affect the concrete.
 - The contractor is responsible for the proper design of all formwork and shoring. Design shall be performed by a licensed engineer.
 - Coordinate locations of all openings, embeds and accessories that are required by all trades. No opening or sleeve may be placed in beams or columns unless approved by the engineer.
 - Proper placement of all embeds, anchor bolts, and etc shall be verified prior to placing the concrete. Notify the engineer of any conflicts.

- STRUCTURAL STEEL**
- Codes and Standards:
 - AISC "Specifications for the Design, Fabrication and Erection of Structural Steel for Buildings," - Latest Edition.
 - Welds shall conform to the American Welding Society, AWS D1.1 using E70 electrodes.
 - Bolts and bolted connections shall conform to "Specifications for Structural Joints Using ASTM A325 or A490 Bolt" Use bearing type bolts with threads across the shear plane.
 - Structural steel shapes, plates, channels, angles - ASTM A36
 - W-shapes - ASTM A992 Grade 50
 - Steel tubing - ASTM A501
 - Steel pipe - ASTM A53, Type E or S, Grade B
 - Anchor bolts - ASTM F1554 (U.N.O.) w/ nuts and washers.
 - Column splices - AISC "Structural Steel Detailing" Table A-7 Page 11-A12.
 - No splices shall be allowed in any structural steel member unless shown on approved shop drawings.
 - Framing connections shall be double angle type (UNO). Design connections for 55% of the total load capacity derived from the uniform load constants table, Part 2 of the AISC Code.
 - Verify the location and size of all floor and roof openings with the appropriate sub-contractor.
 - All members except those to be field welded shall receive one coat of shop primer point. See architectural drawings for preferred color.
 - Steel stairs shall be designed by a licensed engineer retained by the fabricator for a live load = 100 PSF.
 - No openings shall be allowed in steel members unless shown on the drawings.
 - Openings, copes, and other steel cutting shall have a 1/2" minimum radius.
 - All beams shall be fabricated and erected with the natural camber up.
 - Welds not designed shall be a fillet weld equal to 1/16" less than the least thick member, all welds shall be cleaned and painted.
 - Non-shrink grout (ASTM C 1107) to be 6000 psi (min), non-ferrous and non-corrosive.
 - A qualified testing laboratory shall be retained to perform the following tests:
 - Inspect all steel members and connections
 - Test 50% of full penetration welds.
- Send copy of report to the owner, architect, engineer, and contractor.



1 SECTION
SCALE: 1" = 1'-0"



2 SECTION
SCALE: 1" = 1'-0"