

SECTION 102123 CUBICLE CURTAIN TRACKS

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Surface mounted overhead metal curtain track and guides.

1.02 RELATED REQUIREMENTS

- A. Section 092116 - Gypsum: Track supports above ceiling.

1.03 REFERENCE STANDARDS

- A. ASTM E84 - Standard Test Method for Surface Burning Characteristics of Building Materials; 2023d.
- B. NFPA 701 - Standard Methods of Fire Tests for Flame Propagation of Textiles and Films; 2023, with Errata.
- C. UL 214 - Standard for Tests for Flame Propagation of Fabrics and Films; Underwriters Laboratories Inc.; 1997.

1.04 SUBMITTALS

- A. See Section 013000 - Administrative Requirements, for submittal procedures.
- B. Shop Drawings: Indicate a reflected ceiling plan view of curtain track, hangers and suspension points, attachment details, schedule of curtain sizes.
- C. Manufacturer's Installation Instructions: Indicate special procedures, perimeter conditions requiring special attention .

1.05 DELIVERY, STORAGE, AND HANDLING

- A. Accept curtain materials on site and inspect for damage.
- B. Store curtain materials on site and deliver to Owner for installation when requested.

PART 2 PRODUCTS

2.01 MANUFACTURERS

- A. Curtain Track:
 - 1. A. R. Nelson Co; 1200 CEILING MOUNTED TRACK with No. 12 carriers:
www.arnelson.com.

2.02 TRACKS AND TRACK COMPONENTS

- A. Track: Extruded aluminum sections; one piece per cubicle track run; channel profile.
- B. Track End Stop, Tees, Y's, and Switches: To fit track section.
 - 1. Track Bends: Minimum 12 inch radius; fabricated without deformation of track section or impeding movement of carriers.
- C. Curtain Carriers: Nylon roller to accurately fit track; designed to eliminate bind when curtain is pulled; fitted to curtain to prevent accidental curtain removal; 3 carriers per foot of track length.
- D. Installation Accessories: Types required for specified mounting method and substrate conditions.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that surfaces and supports above ceiling are ready to receive work of this Section.
- B. Verify that field measurements are as indicated on shop drawings.

3.02 INSTALLATION

- A. Install curtain track to be secure, rigid, and true to ceiling line.
- B. Install end cap and stop device.

- C. Install curtains on carriers ensuring smooth operation.

END OF SECTION