EXHAUST FAN SCHEDULE

MARK	---	EF-3.1	EF-3.2	EF-MRI
AREA SERVED	---	PATIENT TOILETS	STAFF TLT JANITOR	MRI PURGE
AIR QUANTITY	CFM	250	425	1200
E.S.P.	IN. H20	0.5	0.5	0.4
FAN TYPE	---	CENTRIFUGAL	CENTRIFUGAL	UPBLAST
FAN SPEED	RPM	1528	1422	1411
DRIVE TYPE	---	DIRECT	DIRECT	DIRECT
INTERLOCK	---	RTU-3	RTU-3	N/A
SOUND CRITERIA	SONES	5.8	9.4	12.2
MOTOR POWER	HP	1/8	1/8	1/4
ELECTRICAL	V/PH/HZ	115/1/60	115/1/60	115/1/60
UNIT LOCATION	---	ROOF	ROOF	ROOF
DUCT CONNECTION	IN.	8 x 8	10 x 10	16 x 14
ROOF OPENING	IN.	13.5 x 13.5	13.5 x 13.5	15.5 X 15.5
WEIGHT (EXCL. CURB)	LB.	60	61	73
UNIT MANUFACTURER	---	COOK	COOK	COOK
UNIT MODEL NO.	---	90C15DL	100C15DH	120R15D
NOA NUMBER	---	23-0821.05	23-0821.05	23-0815.03
FL PRODUCT APPROVAL NO.	---	SD080717-11	SD080717-11	SD080717-12
NOTES	---	1,2,3	1,2,3	1,2,4,5

4/27/26 2:17 PM

SCHEDULE NOTES:

1. PROVIDE DISCONNECT SWITCH, BACKDRAFT DAMPER, AND FAN SPEED CONTROLLER.
2. ROOF MOUNTED FANS SHALL BE LISTED FOR HIGH WIND APPLICATION WITH MINIMUM 14"H INSULATED ROOF CURB. INSTALL PER MANUFACTURER NOA SECUREMENT DETAILS. COORDINATE WITH ROOF SLOPE WHERE APPLICABLE.
3. INTERLOCKED EXHAUST FANS SHALL BE WIRED SUCH THAT THEY RUN CONTINUOUSLY WITH RESPECTIVE ROOFTOP UNIT AND SHUT DOWN UPON MANUAL OR AUTOMATIC SHUTDOWN OF ASSOCIATED RTU.
4. PROVIDE DUCT EXTENSION SUCH THAT DUCT TERMINATES AT LEAST AT LEAST 3'-0" ABOVE THE BOTTOM OF RTU FRESH AIR INTAKES.
5. AUTOMATIC OPERATION OF THE MRI EMERGENCY EXHAUST SYSTEM SHALL BE TIED TO THE MRI EMERGENCY ALARM SYSTEM BY AN ELECTRIC RELAY, THE OXYGEN SENSOR, AND THE MANUAL SWITCH/ALARM.

DUCTLESS HEAT PUMP UNIT SCHEDULE

INDOOR UNIT	AC-EQP
AREA SERVED	MRI EQUIPMENT
MANUFACTURER	GREE
MODEL NO.	VIR18HP230V1R32AH
TYPE	WALL-MOUNTED
TOTAL CFM (MAX.)	589
O.A. CFM	0
ELECTRICAL (V/PH/HZ)	THRU OUTDOOR UNIT
FAN POWER (W)	60
DIMENSIONS LxWxH (IN.)	38 x 9 x 12
WEIGHT (LB)	29
OUTDOOR UNIT	**HP-EQP**
MODEL NO.	VIR18HP230V1R32AO
HEATING CAP. @17°F BTUH	14,700
HSPF2	9.0
COOL CAP TOTAL BTUH	18,000
COOL CAP SENSIBLE BTUH	14,040
ENERGY EFFICIENCY (SEER2)	24.5
O.A.D.B. °F	95
MAX. LINE SET LENGTH (FT)	131
LINE SET SIZE: LIQUID - GAS (IN.)	1/4 - 5/8
ELECTRICAL (V/PH/HZ)	208/1/60
MCA (AMPS)	16
MAX FUSE (AMPS)	20
DIMENSIONS LxWxH (IN.)	38 x 16 x 26
WEIGHT (LB)	95

4/27/26 2:17 PM

SCHEDULE NOTES:

1. PROVIDE UNIT WITH WALL MOUNTED 7-DAY PROGRAMMABLE THERMOSTAT.
2. PROVIDE UNIT WITH SINGLE POINT ELECTRICAL CONNECTION AT OUTDOOR UNIT. ELECTRICAL CONTRACTOR TO RUN POWER FROM OUTDOOR UNIT TO INTERIOR UNIT AS REQUIRED BY MANUFACTURER.
3. CONDENSATE PUMP WITH OVERFLOW PROTECTION. PROVIDE RECEPTACLE WITHIN 4 FT OF CONDENSATE PUMP.
4. REFRIGERANT TYPE R32.
5. UNIT PERFORMANCE SHALL MEET MINIMUM ENERGY EFFICIENCY REQUIREMENTS OF ASHRAE 90.1.
6. WASHABLE FILTER.
7. PROVIDE WALL BRACKET FOR MOUNTING OF INDOOR UNIT.
8. OUTDOOR UNIT SHALL BE ATTACHED TO ALUMINUM EQUIPMENT STAND PER MANUFACTUER DETAILS IN COMPLIANCE WITH FBC WINDLOAD REQUIREMENTS.
9. PROVIDE OUTDOOR UNIT WITH NEMA-3R DISCONNECT SWITCH. PROVIDE INDOOR UNIT WITH TOGGLE DISCONNECT SWITCH.
10. VERIFY REFRIGERANT LINE SIZE WITH MANUFACTURER PER FINAL REFRIGERANT RUN. SUCTION AND LIQUID LINES ARE TO BE INSULATED.

DX PACKAGED ROOFTOP UNIT SCHEDULE

MARK		RTU-3
AREA SERVED		CLINIC
LOCATION		ROOF
MANUFACTURER		AAON
MODEL NUMBER		RN-030
FILTERS		
PRE-FILTER TYPE 1	---	2" MERV-8
PRESSURE DROP CLEAN	IN. WTR	0.1
PRESSURE DROP DIRTY	IN. WTR	0.3
PRE-FILTER TYPE 2	---	4" MERV-13
PRESSURE DROP CLEAN	IN. WTR	0.42
PRESSURE DROP DIRTY	IN. WTR	0.7
SUPPLY FAN		
SUPPLY AIR	CFM	8,950
OUTSIDE AIR	CFM	1,000
EXTERNAL STATIC PRESSURE	IN. WTR	1.75
SUPPLY FAN MOTOR	HP/BHP	15 / 10.56
SUPPLY FAN SPEED	RPM	1488
COOLING		
COOLING CAPACITY (NET)	MBH	307.47
SENSIBLE CAPACITY (NET)	MBH	217.62
COOLING COIL	ROWS/FINS	6 / 12
MAX. FACE VELOCITY	FPM	458
ENT. AIR TEMP. DB/WB	°F/°F	78.0 / 65.2
LVG. AIR TEMP. DB/WB (COIL)	°F/°F	52.5 / 52.0
CONDENSER AMBIENT TEMP.	°F	95
EACH CONDENSER FAN MTR	HP	1
QUANTITY	---	3
MINIMUM EER/IEER	BTUH/W	10.9 / 13.2
HEATING		
HEATING CAPACITY	KW	NONE
STAGES		-
HOT GAS REHEAT		
HGR CAPACITY	MBH	211
LVG. AIR TEMP. DB/WB (COIL)	°F/°F	73.9 / 60.5
ELECTRICAL DATA		
ELECTRICAL	V/HZ/PH	460/60/3
MCA	AMPS	84
MOCP	AMPS	100
SCCR	kA	10
CONTROL	---	FACTORY
CONNECTION TYPE	---	VFD / DISC.
CONNECTION QUANTITY	---	SINGLE POINT
POWER TYPE	---	NORMAL
PHYSICAL DATA		
UNIT DIMENSIONS LxWxH	IN.	138 x 101 x 59
OP. WEIGHT (EXCL. CURB)	LBS	2,784

12/8/23 3:05 PM

SCHEDULE NOTES:

1. 2X DIGITAL SCROLL COMPRESSORS FOR CAPACITY MODULATION.
2. STAINLESS STEEL DRAIN PAN WITH CONDENSATE OVERFLOW SWITCH.
3. DOUBLE WALL CONSTRUCTION WITH MINIMUM R-13 INSULATION.
4. PHASE AND BROWN OUT PROTECTION.
5. 5 MIN TIME DELAY RELAY & 20 SEC TIME DELAY RELAY.
6. CONDENSER FAN CYCLING FOR LOW AMBIENT CONTROL.
7. UNIT MOUNTED SUPPLY FAN VFD WITH BYPASS.
8. INTAKE HOOD WITH 1/2" METAL MESH SCREEN. FULLY MODULATING MOTORIZED OA DAMPER INTERLOCKED WITH SUPPLY FAN. PROVIDE WITH OA DAMPER CONTROL.
9. MINIMUM 16" HIGH INSULATED ROOF CURB SUCH THAT OA INTAKE IS MINIMUM OF 36" ABOVE FINISHED ROOF. ROOF CURB SHALL INCLUDE KINETICS KIP RT RAILS FOR VIBRATION ISOLATION. COORDINATE CURB WITH ROOF PITCH.
10. PRE-FILTERS UPSTREAM OF COOLING COIL.
11. FILTER SECTION WITH UNIT MOUNTED MAGNEHELIC GAUGE WITH OUTPUT TO BAS. RELAYS BY CONTROLS CONTRACTOR AS NEEDED. PROVIDE "CLEAN" AND "DIRTY" INDICATORS.
12. CONDENSER HAIL GUARD AND ECM CONDENSER FAN HEAD PRESSURE CONTROL.
13. NEMA 3R DISCONNECT BY DIVISION 26.
14. BOTTOM SUPPLY, BOTTOM RETURN.
15. MANUFACTURER SHALL PROVIDE WINDLOAD CALCULATIONS WITH SIGNED AND SEALED STRUCTURAL DETAILS FOR EQUIPMENT TIE-DOWN IN COMPLIANCE WITH FBC WINDLOAD REQUIREMENTS.
16. CONTRACTOR IS RESPONSIBLE FOR ANY DEVIATIONS FROM BASIS OF DESIGN THAT IMPACT ELECTRICAL OR STRUCTURAL INCLUDING COMPENSATION TO EOR FOR CHANGES TO CONSTRUCTION DOCUMENTS AS A RESULT OF ALTERNATE MANUFACTURERS.
17. 115V FACTORY WIRED CONVENIENCE OUTLET.
18. SINGLE POINT POWER WITH AUTOMATIC RESTART OF CONDENSERS AFTER LOSS OF POWER.
19. MANUFACTURER TO PROVIDE LINE REACTOR OR OTHER PROTECTIVE DEVICES TO MEET THE AVAILABLE FAULT CURRENT INDICATED ON THE ELECTRICAL DRAWINGS. IN THE EVENT INFORMATION IS NOT PROVIDED, ASSUME 10,000 AIC.
20. UNIT CONTROLLER SHALL INCLUDE:
 LCD DISPLAY WITH USER INTERFACE
 DIGITAL COMPRESSOR MODULATION AND COMPRESSOR STAGING
 OUTDOOR AIR MONITORING AND OUTDOOR AIR DAMPER CONTROL
 HUMIDITY SENSOR POLLING TO CREATE HIGHEST PRIORITY FOR SYSTEM ADAPTIVE SUPPLY AIR TEMPERATURE RESET BASED ON RETURN AIR TEMP.
 FAN PROVING INTERLOCK
 DIRTY FILTER ALARM (TWO LOCATIONS FOR UNITS WITH FINAL FILTERS)
 EMERGENCY SHUTDOWN INPUT (SMOKE DETECTOR, FIRE ALARM)
 VAV UNIT CONTROL.
21. AIR FLOW MONITORING STATION FOR OUTSIDE AIR FLOW MONITORING.
22. MODULATING HOT GAS REHEAT FOR HUMIDITY CONTROL.
23. ANY DEVIATIONS FROM SCHEDULE OR SPECIFICATION SHALL BE NOTED IN THE SUBMITTAL PACKAGE.

CONSTANT / VARIABLE AIR VOLUME BOX SCHEDULE

WITH ELECTRIC HEAT

MARK	B3.1	B3.2	B3.3	B3.4	B3.5	B3.6	B3.7	B3.8	B3.9	B3.10	B3.11	B3.12	B3.13	B3.14	B3.15	B3.16	B3.17	B3.18	B3.19	B3.20
AREA SERVED	TELEMEDICINE	BILLING	OBSERVATION ROOM	PATIENT SERVICES	EAST EXAMS	NORTH EXAMS	TEAM STATION (E)	IT CLOSET	SOUTH EXAMS	TEAM STATION (W)	CONFERENCE	RECEPTION	OFFICE 327	OFFICE/REC.	SCHEDULING	X-RAY ROOM	CIRC/TLTS	MRI CONTROL	MRI SCAN	LOBBY
AIR CFM - MAXIMUM	675	300	275	400	925	300	675	150	400	500	300	200	175	300	450	250	700	175	600	1200
AIR CFM - MIN. OCCUPIED	350	150	150	200	475	150	350	75	200	250	175	100	125	150	225	210	350	90	300	450
AIR CFM - MIN. UNOCCUPIED	350	150	150	200	475	150	350	75	200	250	175	100	125	150	225	210	350	90	300	450
MANUFACTURER	ENVIRO-TEC	ENVIRO-TEC	ENVIRO-TEC	ENVIRO-TEC	ENVIRO-TEC	ENVIRO-TEC	ENVIRO-TEC	ENVIRO-TEC	ENVIRO-TEC	ENVIRO-TEC	ENVIRO-TEC	ENVIRO-TEC	ENVIRO-TEC	ENVIRO-TEC	ENVIRO-TEC	ENVIRO-TEC	ENVIRO-TEC	ENVIRO-TEC	ENVIRO-TEC	ENVIRO-TEC
MAX. UNIT PD IN. WC	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5
MIN. INLET SP IN. WC	0.04	0.04	0.01	0.06	0.03	0.04	0.04	0.01	0.06	0.03	0.04	0.01	0.01	0.04	0.02	0.01	0.06	0.01	0.04	0.06
ENTERING AIR TEMP °F	53	53	53	53	53	53	53	53	53	53	53	53	53	53	53	53	53	53	53	53
LEAVING AIR TEMP °F HEAT	80	85	85	85	85	85	80	53	85	80	85	85	95	85	80	80	80	85	85	80
HEATING CAPACITY - KW	3	1.5	1.5	2	5	1.5	3	NONE	2	2	1.5	1	1.5	1.5	2	1.5	3	1	3	3
STEPS CONTROL	SCR	SCR	SCR	SCR	SCR	SCR	SCR	N/A	SCR	SCR	SCR	SCR	SCR	SCR	SCR	SCR	SCR	SCR	SCR	SCR
ELECTRICAL - V/PH	277/1	277/1	277/1	277/1	480/3	277/1	277/1	N/A	277/1	277/1	277/1	277/1	277/1	277/1	277/1	277/1	277/1	277/1	277/1	277/1
AMPS	10.83	5.42	5.42	7.22	6.02	5.42	10.83	N/A	7.22	7.22	5.42	3.61	5.42	5.42	7.22	5.42	10.83	3.61	10.83	10.83

12/8/23 3:05 PM

SCHEDULE NOTES:
BASIS OF DESIGN:
ENVIRO-TEC MODEL SDR-EH PRESSURE INDEPENDENT
DOUBLE WALL CONSTRUCTION W/ 3/4" 4LB/FT3 INSULATION.
TOP AND BOTTOM ACCESS PLATES

COORDINATE WITH CONTROL SYSTEM INSTALLER FOR APPROPRIATE SELECTION OF THERMOSTATS AND COORDINATE WITH TEMPERATURE CONTROL SYSTEM FOR DDC OPERATION.

CONTROL SYSTEM SUPPLIER WILL PROVIDE DDC CONTROLLERS FOR FACTORY INSTALLATION.

PROVIDE NECESSARY CLEARANCE FOR MAINTENANCE.

WHERE RUNOUT SIZE IS SHOWN ON DRAWING, FOLLOW DRAWING. EQUIVALENT RECTANGLAR DUCT SIZES MAY BE USED.

MRI CHILLER SCHEDULE

MARK		CH-MRI
LOCATION		ROOF
MANUFACTURER		HASKRIS
MODEL NUMBER		OPC24
CAPACITY (NET)	BTUH	214,965
AMBIENT TEMP	DEG F	95
COOLER		
WATER FLOWRATE (@ 75 PSI)	GPM	29
PROPYLENE GLYCOL QUANTITY	%	40
MAX PUMP PRESSURE	FT WC	---
NO. OF CONDENSER FANS		2
ELECTRICAL DATA		
ELECTRICAL	V/PH/HZ	460/3/60
MCA	A	56.8
MOCP	A	70
CONNECTION TYPE		STARTER / DISCONNECT
CONNECTION QUANTITY		SINGLE POINT
POWER TYPE		NORMAL
UNIT INFORMATION		
UNIT DIMENSIONS LxWxH	IN.	76.5 x 41.8 x 73.9
UNIT WEIGHT (OPERATING)	LB.	1860
AREA SERVED		CLINIC MRI EQUIP

5/4/26 1:21 PM

SCHEDULE NOTES:

1. MRI CHILLER SUPPLIED BY GE AND INSTALLED BY MECHANICAL CONTRACTOR.
2. REFER TO PLANS, DETAILS, AND SPECIFICATIONS FOR ACCESSORIES, PIPE MATERIAL, AND PIPING CONNECTIONS.
3. CHILLER SYSTEM SHALL BE CHARGED WITH 50% PROPYLENE GLYCOL PER MANUFACTURER REQUIREMENTS.
4. R454B REFRIGERANT.
5. STANDARD FEATURES INCLUDE DUAL CENTRIFUGAL PUMPS, VARIABLE SPEED EC FANS, AND CIRCUIT BREAKERS.
6. CHILLER INFORMATION SHOWN FOR REFERENCE ONLY. MECHANICAL CONTRACTOR SHALL VERIFY SITE SPECIFIC CHILLER MANUFACTURER, MODEL #, DIMENSIONS, AND ELECTRICAL REQUIREMENTS WITH EQUIPMENT VENDOR AND SIEMENS PRIOR TO ROUGHING IN EQUIPMENT.

AIR TERMINAL SCHEDULE

SYMBOL	ADAPTER / NECK SIZE	FACE SIZE	SLOT WIDTH	NO. OF SLOTS	MAX CFM	MAX NC	MAX SP	THROW	RUNOUT SIZE	MANUFACTURER/MODEL NO.
EAA	6"x6"	8"x8"	---	---	75	28	.04	---	6"Ø/8"x4"	TITUS 50-F WITH EGG-CRATE CORE
EBB	8"x8"	10"x10"	---	---	200	28	.05	---	8"Ø/10"x6"	TITUS 50-F WITH EGG-CRATE CORE
EF	18"x18"	24"x24"	---	---	1250	27	.07	---	16"Ø/24"x10"	TITUS 50-F WITH EGG-CRATE CORE
RA	6"x6"	24"x24"	---	---	75	28	.04	---	6"Ø/8"x4"	TITUS 50-F WITH EGG-CRATE CORE
RB	8"x8"	24"x24"	---	---	200	28	.05	---	8"Ø/10"x6"	TITUS 50-F WITH EGG-CRATE CORE
RBB	8"x8"	10"x10"	---	---	200	28	.05	---	8"Ø/10"x6"	TITUS 50-F WITH EGG-CRATE CORE
RC	10"x10"	24"x24"	---	---	300	27	.05	---	10"Ø/14"x6"	TITUS 50-F WITH EGG-CRATE CORE
RD	12"x12"	24"x24"	---	---	540	28	.06	---	12"Ø/16"x8"	TITUS 50-F WITH EGG-CRATE CORE
RE	14"x14"	24"x24"	---	---	700	28	.07	---	14"Ø/18"x8"	TITUS 50-F WITH EGG-CRATE CORE
RF	18"x18"	24"x24"	---	---	1250	27	.07	---	16"Ø/24"x10"	TITUS 50-F WITH EGG-CRATE CORE
RLF	12"Ø	48"x5"	2"	1	460	20	.1	SLOT	12"Ø/14"x8"	TITUS FL-10
RLK	10"Ø	60"x8"	1"	3	300	25	.1	SLOT	10"Ø/10"x8"	TITUS ML-39
RPB	---	24"x24"	---	---	1500	---	---	---	---	TITUS 50-F WITH EGG-CRATE CORE
SA	6"Ø/6"x6"	24"x24"	---	---	75	20	.07	4-WAY BLOW	6"Ø/8"x4"	TITUS TDC
SAA	6"Ø/6"x6"	12"x12"	---	---	75	20	.07	4-WAY BLOW	6"Ø/8"x4"	TITUS TDC
SB	8"Ø/9"x9"	24"x24"	---	---	230	20	.07	4-WAY BLOW	8"Ø/10"x6"	TITUS TDC
SBB	8"Ø/9"x9"	15"x15"	---	---	230	20	.07	4-WAY BLOW	8"Ø/10"x6"	TITUS TDC
SC	10"Ø/12"x12"	24"x24"	---	---	420	25	.08	4-WAY BLOW	10"Ø/12"x8"	TITUS TDC
SG	8"Ø/9"x9"	24"x24"	---	---	220	27	.09	3-WAY BLOW	8"Ø/10"x6"	TITUS TDC
SLC	12"Ø	60"x8"	1"	4	600	25	.65	SLOT	12"Ø	TITUS ML-39
SLD	6"Ø	24"x4"	1"	1	50	25	.1	SLOT	6"Ø	TITUS FL-10
SLF	8"Ø	48"x4"	1"	1	175	20	.1	SLOT	8"Ø	TITUS FL-10
SLG	8"Ø	60"x4"	1"	1	225	20	.1	SLOT	8"Ø	TITUS FL-10
SLJ	8"Ø	48"x8"	1"	1	130	25	.1	SLOT	8"Ø	TITUS ML-39

2

AIR TERMINAL PERFORMANCE NOTES:

1. CONTRACTOR TO USE DUCT SPIN-IN FITTINGS WITH MANUAL VOLUME DAMPER EQUIVALENT TO GENFLEX MODEL SM-2DEL OR APPROVED EQUIVALENT.
2. FACE SIZE FOR CEILING MOUNTED AIR TERMINALS SHALL BE 24"x24" IN ALL LAY IN CEILING LOCATIONS TO FIT WITHIN GRIDS UNLESS OTHERWISE SPECIFIED.
3. LINEAR SLOT DIFFUSERS AND RETURNS (ML-39) SHALL BE CONCEALED MOUNT TYPE WITH ADJUSTABLE DISCHARGE. PROVIDE INSULATED PLENUM - MPI-39 FOR ALL SUCH LINEAR SLOT DIFFUSERS.
4. LINEAR SLOT DIFFUSERS AND RETURNS (FL-10) SHALL BE FRAMELESS MOUNT TYPE. PROVIDE EITHER HIGH THROW OR JET THROW PATTERN CONTROLLER BASED ON CEILING HEIGHT AND/OR AS SPECIFIED ON FLOORPLAN. PROVIDE INSULATED PLENUM - FBP FOR ALL SUCH LINEAR SLOT DIFFUSERS AND RETURNS. DIFFUSERS INSTALLED WITHIN INTEGRATED RECESSED SLOT IN LOBBY SHALL HAVE SXX OR ECXX END CONDITION. FOR DIFFUSERS INSTALLED WITHIN INTEGRATED RECESSED SLOT, DIFFUSER LENGTH MUST BE 1.5" SHORTER THAN NOMINAL LENGTH; COORDINATE WITH VENDOR FOR EXACT REQUIREMENTS. DIFFUSERS INSTALLED WITHIN RECEPTION OR PATIENT TOILET AREAS SHALL BE FRAMELESS (BORDER TYPE 55).
5. LINEAR SLOT DIFFUSERS AND RETURNS (ML-39) SHALL BE CONCEALED MOUNT TYPE WITH ADJUSTABLE DISCHARGE. PROVIDE INSULATED PLENUM - MPI-39 FOR ALL SUCH LINEAR SLOT DIFFUSERS AND RETURNS.
6. FOR HARD CEILING APPLICATIONS, FACE SIZE SHALL EQUAL NECK SIZE. COORDINATE WITH ARCHITECTURAL CEILING PLAN.

I.C. Thomasson Associates, Inc.
CONSULTING ENGINEERS
3031 N. ROCKY POINT DR. W., SUITE 750
TAMPA, FL. 33607
PHONE (813) 882-4415
WWW.ICTHOMASSON.COM
ICT PROJECT NO. 230427.00
FIRM CERTIFICATE OF AUTHORIZATION
FLORIDA REG. #C.A.-0001276
MECHANICAL ENGINEER
DAN A. NESMAN, P.E.
FLORIDA #54088
ELECTRICAL ENGINEER
PHILIP GARRETT, P.E.
FLORIDA #63289

SEAL

This item has been digitally signed and sealed by Daniel A. Nesman on the date adjacent to the seal.

Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.

Digitally signed by Daniel Allen Nesman
DN: E=Dan.Nesman@SalasOBrien.com, CN=Daniel Allen Nesman, O=I.C. Thomasson Associates, L=Nashville, S=TN, SERIALNUMBER=MAS2026011674409 1, C=US
Location: Tampa, FL
Contact Info: 8138024415
Date: 2026.08.03 15:08:39-04'00'

DEUK SPINE INSTITUTE
Surgery Center at Millenia, LLC

Hunton Brady ARCHITECTS

DATE	SUBMISSION	NO
12.12.2023	CONSTRUCTION DOCUMENTS	
05.19.2026	CCD NO. 1	1
08.07.2026	CCD #2R	2

MECHANICAL SCHEDULES

PROJ. NO. H-23016.00 **SHEET**
DRAWN OA
M700B

Copyright ©2023, HuntonBrady Architects, PA
Copyright HuntonBrady Architects P.A. All Rights Reserved. 333 S. Garland Ave., Suite 1100, Orlando, Florida 32801 (407) 839-0886 (407) 839-1709/Fax www.huntonbrady.com License AR91515