DOOR SCHEDULE

DOOR NO.	ROOM NO.	LOCATION	TYPE (REFER TO A-6.1)	DOOR SIZE (D.S.) W x H (1 3/4" THICK)	DOOR MATERIAL	DOOR FINISH	FRAME MATERIAL (TYPE OPENING)	FRAME FINISH	FRAME SIZE			FRAME DETAILS			DOOR AND FRAME FIRE RATING	HARDWARE	REMARKS: REFER TO SPECIFICATIONS FOR FURTHER INFORMATION	DOOR NO.
									JAMB	HEAD	DEPTH	JAMB	HEAD	SILL				
101A 101B	101 101	SALES NOT USED	D-6	3'-0" x 7'-0"	HOLLOW METAL GALVANIZED 18 GA.	PAINTED	HOLLOW METAL GALVANIZED 16 GA. (CMU)	PAINT	2"	4"	5 3/4"	4C/6.11	4B/6.11	4A/6.11	N/A	REFER TO SPECIFICATIONS SECTION 08711	PEMKO – RAIN CAP #346C–LAR OR NATIONAL GUARD DRIP STRIP #16 A 40" TRIMCO–PULL # 1821XUS32D	101A
101C 101P	101	SALES NOT USED	SF-2	REFER TO NOTE #3 ON A-6.11	ALUMINUM	CLEAR	ALUMINUM	CLEAR	N/A	N/A	N/A	6/6.11	5B/6.11	5A/6.11	N/A	REFER TO SPECIFICATIONS SECTION 08711	BI–PARTING SLIDING DOORS. INSIDE SLIDE WITH BREAKAWAY DOORS AND SIDELIGHTS; PROVIDE AUTO. OVERHEAD OPENER; TWO WAY TRAFFIC.IMPACT RATED.	101C
101D 101R	101	SALES NOT USED	SF-2	REFER TO NOTE #3 ON A-6.11	ALUMINUM	CLEAR	ALUMINUM	CLEAR	N/A	N/A	N/A	6/6.11	5B/6.11	5A/6.11	N/A	REFER TO SPECIFICATIONS SECTION 08711	BI–PARTING SLIDING DOORS. INSIDE SLIDE WITH BREAKAWAY DOORS AND SIDELIGHTS; PROVIDE AUTO. OVERHEAD OPENER; TWO WAY TRAFFIC. IMPACT RATED.	101D
101E	101	SALES	D-6	3'-0" x 7'-0"	HOLLOW METAL GALVANIZED 18 GA.	PAINTED	HOLLOW METAL GALVANIZED 16 GA. (CMU)	PAINT	2"	4"	5 3/4"	4C/6.11	4B/6.11	4A/6.11	N/A	REFER TO SPECIFICATIONS SECTION 08711	TRIMCO–PULL # 1821XUS32D	101E
101F	101	SALES	D-6	3'-0" x 7'-0"	HOLLOW METAL GALVANIZED 18 GA.	PAINTED	HOLLOW METAL GALVANIZED 16 GA. (CMU)	PAINT	2"	4"	5 3/4"	4C/6.11	4B/6.11	4A/6.11	N/A	REFER TO SPECIFICATIONS SECTION 08711	PEMKO – RAIN CAP #346C–LAR OR NATIONAL GUARD DRIP STRIP #16 A 40" TRIMCO–PULL # 1821XUS32D	101F
101G	101	SALES	D-6	3'-0" x 7'-0"	HOLLOW METAL GALVANIZED 18 GA.	PAINTED	HOLLOW METAL GALVANIZED 16 GA. (CMU)	PAINT	2"	4"	5 3/4"	4C/6.11	4B/6.11	4A/6.11	N/A	REFER TO SPECIFICATIONS SECTION 08711	PEMKO – RAIN CAP #346C–LAR OR NATIONAL GUARD DRIP STRIP #16 A 40" TRIMCO–PULL # 1821XUS32D	101G
101H	101	SALES	D-7	3'-0" x 7'-0"	HOLLOW METAL GALVANIZED 18 GA.	PAINTED	HOLLOW METAL GALVANIZED 16 GA. (CMU)	PAINT	2"	4"	5 3/4"	4C/6.11	4B/6.11	4A/6.11	N/A	REFER TO SPECIFICATIONS SECTION 08711	4" X 24" VIEW WINDOW WITH METAL FRAME WITH 1/4" THICK CLEAR TEMPERED GLASS; TRIMCO–PULL # 1821XUS32D	101H
101J	101	SALES	D-12	18'-0" x 14'-0"	GALVANIZED STEEL	FACTORY FINISH	MANUFACTURER'S STANDARD	PAINT	MFR. STD.	MFR. STD.	N/A	2C/6.11 SIM.	2B/6.11 SIM.	N/A	N/A	REFER TO SPECIFICATIONS SECTION 08711	REFER TO NOTE 1 THIS SHEET	101J
101K 101L 101M	101	NOT USED NOT USED NOT USED																
102A	102	MAIN EXIT VESTIBULE	SF-3	REFER TO NOTE #3 ON A-6.11	ALUMINUM	CLEAR	ALUMINUM	CLEAR	N/A	N/A	N/A	6/6.11	5D/6.11	5A/6.11	N/A	REFER TO SPECIFICATIONS SECTION 08711	BI–PARTING SLIDING DOORS. INSIDE SLIDE WITH BREAKAWAY DOORS AND SIDELIGHTS. PROVIDE AUTO. OVERHEAD OPENER, TWO WAY TRAFFIC	102A
102B	102	MAIN EXIT VESTIBULE	SF-1	REFER TO NOTE #3 ON A-6.11	ALUMINUM	CLEAR	ALUMINUM	CLEAR	N/A	N/A	N/A	6/6.11	5C/6.11	5A/6.11	N/A	REFER TO SPECIFICATIONS SECTION 08711	BI–PARTING SLIDING DOORS (IMPACT RATED). INSIDE SLIDE WITH BREAKAWAY DOORS AND SIDELIGHTS AND TRANSOM PANEL. PROVIDE AUTO. OVERHEAD OPENER, EXIT ONLY TRAFFIC IMPACT RATED.	102B
103	103	BREAKROOM	D-3	3'-6" x 7'-0"	WOOD	FACTORY FINISH CLEAR	HOLLOW METAL (DRYWALL)	PAINT	2"	2"	5 3/4"	1C/6.11	1B/6.11	1A/6.11	N/A	REFER TO SPECIFICATIONS SECTION 08711	UNDERCUT DOOR 3/4"; 4"x25" VIEW WINDOW WITH METAL FRAME WITH 1/4" THICK CLEAR TEMPERED GLASS	103
103B		NOT USED																
104	104	AP OFFICE	D-1	3'-0" x 7'-0"	WOOD	FACTORY FINISH CLEAR	HOLLOW METAL (CMU)	PAINT	2"	4"	5 3/4"	3C/6.11	3B/6.11	3A/6.11	N/A	REFER TO SPECIFICATIONS SECTION 08711	UNDERCUT DOOR 3/4"	104
105		NOT USED																
106		NOT USED																
107	107	MONEY	D-2	3'-0" x 7'-0"	WOOD	FACTORY FINISH CLEAR	HOLLOW METAL (CMU)	PAINT	2"	4"	5 3/4"	3C/6.11	3B/6.11	3A/6.11	N/A	REFER TO SPECIFICATIONS SECTION 08711	UNDERCUT DOOR 3/4", PROVIDE PEEP–HOLE SIGHT GLASS HARDWARE "IVES" 698B 26D AT 5'–0" A.F.F.	107
108	108	PICKUP	D-6	3'-0" x 7'-0"	HOLLOW METAL GALVANIZED 14 GA.	PAINTED	HOLLOW METAL GALVANIZED 16 GA. (CMU)	PAINT	2"	4"	5 3/4"	4C/6.11	4B/6.11	4A/6.11	N/A	REFER TO SPECIFICATIONS SECTION 08711		108
109	109	NOT USED																
110	110	NOT USED																
111A	111	MAIN ENTRY VESTIBULE	SF-3	REFER TO NOTE #3 ON A-6.11	ALUMINUM	CLEAR	ALUMINUM	CLEAR	N/A	N/A	N/A	6/6.11	5B/6.11 SIM.	5A/6.11	N/A	REFER TO SPECIFICATIONS SECTION 08711	BI–PARTING SLIDING DOORS. INSIDE SLIDE WITH BREAKAWAY DOORS AND SIDELIGHTS. PROVIDE AUTO. OVERHEAD OPENER, ENTRANCE ONLY TRAFFIC	111A
111B	111	MAIN ENTRY VESTIBULE	SF-1	REFER TO NOTE #3 ON A-6.11	ALUMINUM	CLEAR	ALUMINUM	CLEAR	N/A	N/A	N/A	6/6.11	5C/6.11	5A/6.11	N/A	REFER TO SPECIFICATIONS SECTION 08711	BI–PARTING SLIDING DOORS (IMPACT RATED). INSIDE SLIDE WITH BREAKAWAY DOORS AND SIDELIGHTS AND TRANSOM PANEL. PROVIDE AUTO. OVERHEAD OPENER, ENTRANCE ONLY TRAFFIC IMPACT RATED.	111B
112	112	ELECTRICAL ROOM #2	D-5	3'-0" x 7'-0"	WOOD	FACTORY FINISH CLEAR	HOLLOW METAL (DRYWALL)	PAINT	2"	2"	5 3/4"	1C/6.11	1B/6.11	1A/6.11	N/A	REFER TO SPECIFICATIONS SECTION 08711	REFER TO NOTE 2 THIS SHEET	112
113	113	MANAGER'S	D-1	3'-0" x 7'-0"	WOOD	FACTORY FINISH CLEAR	HOLLOW METAL (DRYWALL)	PAINT	2"	2"	5 3/4"	1C/6.11	1B/6.11	1A/6.11	N/A	REFER TO SPECIFICATIONS SECTION 08711	UNDERCUT DOOR 3/4"	113
114	114	TELE/DATA	D-6	3'-0" x 7'-0"	HOLLOW METAL GALVANIZED 18 GA.	PAINTED	HOLLOW METAL (CMU)	PAINT	2"	4"	5 3/4"	3C/6.11	3B/6.11	3A/6.11	N/A	REFER TO SPECIFICATIONS SECTION 08711		114
115	115	SPRINKLER ROOM	D-6	3'-8" x 7'-0"	HOLLOW METAL GALVANIZED 18 GA.	PAINTED	HOLLOW METAL GALVANIZED 16 GA. (CMU)	PAINT	2"	4"	5 3/4"	4C/6.11	4B/6.11	4A/6.11	N/A	REFER TO SPECIFICATIONS SECTION 08711	PEMKO – RAIN CAP #346C–LAR OR NATIONAL GUARD DRIP STRIP #16 A 48"	115
116	116	CART STORAGE	D-10	8'-0" x 7'-4"	GALVANIZED STEEL	FACTORY FINISH	MANUFACTURER'S STANDARD	PAINT	MFR. STD.	MFR. STD.	N/A	2C/6.11 SIM.	2B/6.11	—	N/A	REFER TO SPECIFICATIONS SECTION 08711	INSULATED SECTIONAL DOOR WITH CHAIN HOIST AND PADLOCK (REFER TO SPECIFICATIONS)	116
117A 117B 117C	117	RECEIVING	D-10	9'-4" x 10'-0"	GALVANIZED STEEL	FACTORY FINISH	MANUFACTURER'S STANDARD	PAINT	MFR. STD.	MFR. STD.	N/A	2C/6.11	2B/6.11	—	N/A	REFER TO SPECIFICATIONS SECTION 08711	INSULATED SECTIONAL DOOR WITH CHAIN HOIST AND PADLOCK (REFER TO SPECIFICATIONS)	117A 117B 117C
117D	117	RECEIVING	D-7	3'-0" x 7'-0"	HOLLOW METAL GALVANIZED 18 GA.	PAINTED	HOLLOW METAL GALVANIZED 16 GA. (CMU)	PAINT	2"	4"	5 3/4"	4C/6.11	4B/6.11	4A/6.11	N/A	REFER TO SPECIFICATIONS SECTION 08711	4" X 25" VIEW WINDOW WITH METAL FRAME WITH 1/4" THICK CLEAR TEMPERED GLASS; TRIMCO–PULL # 1821XUS32D	117D
118	118	RECEIVING/ DELIVERY OFFICE	D-4	3'-0" x 7'-0"	WOOD	FACTORY FINISH CLEAR	HOLLOW METAL (CMU)	PAINT	2"	4"	5 3/4"	3C/6.11	3B/6.11	3A/6.11	N/A	REFER TO SPECIFICATIONS SECTION 08711	UNDERCUT DOOR 3/4"; 18"x36" HALF GLASS WINDOW WITH METAL FRAME WITH 1/4" THICK CLEAR TEMPERED GLASS	118
119A	119	STORAGE	D-6	3'-0" x 7'-0"	HOLLOW METAL GALVANIZED 18 GA.	PAINTED	HOLLOW METAL GALVANIZED 16 GA. (CMU)	PAINT	2"	4"	5 3/4"	4C/6.11	4B/6.11	4A/6.11	N/A	REFER TO SPECIFICATIONS SECTION 08711	PEMKO–RAIN CAP #346C–LAR OR NATIONAL GUARD DRIP STRIP #16 A 40"; TRIMCO–PULL #1821XUS32D	119A
119B	119	STORAGE	D-10	9'-4" x 10'-0"	GALVANIZED STEEL	FACTORY FINISH	MANUFACTURER'S STANDARD	PAINT	MFR. STD.	MFR. STD.	N/A	2C/6.11	2B/6.11	—	N/A	REFER TO SPECIFICATIONS SECTION 08711	INSULATED SECTIONAL DOOR WITH CHAIN HOIST AND PADLOCK (REFER TO SPECIFICATIONS) PROVIDE FULL LAP PLASTIC STRIPS. 1 2	119B
120	120	DISTRICT MANAGER	D-1	3'-0" x 7'-0"	WOOD	FACTORY FINISH CLEAR	HOLLOW METAL (DRYWALL)	PAINT	2"	2"	5 3/4"	1C/6.11	1B/6.11	1A/6.11	N/A	REFER TO SPECIFICATIONS SECTION 08711	UNDERCUT DOOR 3/4"	120
121	121	ELECTRICAL CLOSET #1	D-8	PAIR 2'-6" x 7'-0"	HOLLOW METAL GALVANIZED 18 GA.	PAINTED	HOLLOW METAL GALVANIZED 16 GA. (SHAFTWALL)	PAINT	2"	2"	4 3/4"	1C/6.11 SIM.	1B/6.11 SIM.	1A/6.11 SIM.	1–½ HOUR	REFER TO SPECIFICATIONS SECTION 08711	FLUSH BOLTS–IVES 458–2–626. ASTRAGAL PER DOOR SUPPLIER • (1) CLOSER ON ACTIVE LEAF.	121
122A	122	ELECTRICAL ROOM #1	D-9	4'-0" x 8'-4"	HOLLOW METAL GALVANIZED 18 GA.	PAINTED	HOLLOW METAL (CMU)	PAINT	2"	4"	5 3/4"	3C/6.11	3B/6.11	3A/6.11	N/A	REFER TO SPECIFICATIONS SECTION 08711	24" SQUARE STEEL LOUVERED VENT–18 GA. "Y" BLADE, PRIMED, TO BE PAINTED TO MATCH DOOR FRAME.	122A
122B	122	ELECTRICAL ROOM #1	D-6	3'-0" x 7'-0"	HOLLOW METAL GALVANIZED 18 GA.	PAINTED	HOLLOW METAL GALVANIZED 16 GA. (CMU)	PAINT	2"	4"	5 3/4"	4C/6.11	4B/6.11	4A/6.11	N/A	REFER TO SPECIFICATIONS SECTION 08711	PEMKO–RAIN CAP #346C–LAR OR NATIONAL GUARD DRIP STRIP #16 A 40"; TRIMCO–PULL #1821XUS32D	122B
123A	123	C.L.C. VESTIBULE	D-11	18'-0" x 10'-0"	ALUMINUM	CLEAR	MANUFACTURER'S STANDARD	PAINT	MFR. STD.	MFR. STD.	N/A	2C/6.11	2B/6.11	N/A	N/A	REFER TO SPECIFICATIONS SECTION 08711	REFER TO NOTE 3 THIS SHEET	123A
123B	123	C.L.C. VESTIBULE	SF-2	REFER TO NOTE #3 ON A-6.11	ALUMINUM	CLEAR	ALUMINUM	CLEAR	N/A	N/A	N/A	6/6.11	5B/6.11	5A/6.11	N/A	REFER TO SPECIFICATIONS SECTION 08711	BI–PARTING SLIDING DOORS. INSIDE SLIDE WITH BREAKAWAY DOORS AND SIDELIGHTS PROVIDE AUTO. OVERHEAD OPENER; TWO WAY TRAFFIC IMPACT RATED.	123B
123C	123	NOT USED																123C
123D 123E		NOT USED																
124	124	LOWE'S UNIVERSITY	D-4	3'-0" x 7'-0"	WOOD	FACTORY FINISH CLEAR	HOLLOW METAL (CMU)	PAINT	2"	4"	5 3/4"	3C/6.11	3B/6.11	3A/6.11	N/A	REFER TO SPECIFICATIONS SECTION 08711	UNDERCUT DOOR 3/4"; 18" x 36" HALF GLASS WINDOW WITH METAL FRAME WITH 1/4" THICK CLEAR TEMPERED GLASS	124
125	125	TRAINING ROOM	D-3	3'-0" x 7'-0"	WOOD	FACTORY FINISH CLEAR	HOLLOW METAL (DRYWALL)	PAINT	2"	2"	5 3/4"	1C/6.11	1B/6.11	1A/6.11	N/A	REFER TO SPECIFICATIONS SECTION 08711	UNDERCUT DOOR 3/4"; 4"x25" VIEW WINDOW WITH METAL FRAME WITH 1/4" THICK CLEAR TEMPERED GLASS	125A
126		NOT USED																
127	127	JANITOR'S CLOSET	D-1	3'-6" x 7'-0"	WOOD	FACTORY FINISH CLEAR	HOLLOW METAL (DRYWALL)	PAINT	2"	2"	5 3/4"	1C/6.11	1B/6.11	1A/6.11	N/A	REFER TO SPECIFICATIONS SECTION 08711	UNDERCUT DOOR 3/4"	127
128	128	UNISEX	D-1	3'-0" x 7'-0"	WOOD	FACTORY FINISH CLEAR	HOLLOW METAL (DRYWALL)	PAINT	2"	2"	5 3/4"	1C/6.11	1B/6.11	1A/6.11	N/A	REFER TO SPECIFICATIONS SECTION 08711	UNDERCUT DOOR 3/4"	128
	129 130 131	ALCOVE RESTROOM RESTROOM		NO DOORS REQUIRED														
132	132	ASSISTANT MANAGER	D-1	3'-0" x 7'-0"	WOOD	FACTORY FINISH CLEAR	HOLLOW METAL (DRYWALL)	PAINT	2"	2"	5 3/4"	1C/6.11	1B/6.11	1A/6.11	N/A	REFER TO SPECIFICATIONS SECTION 08711	UNDERCUT DOOR 3/4"	132
	133 134 135	CORRIDOR ALCOVE GARDEN		NO DOORS REQUIRED														

DOOR SCHEDULE NOTES

1. UNINSULATED COILING DOOR WITH MOTOR HOIST (REFER TO SPECIFICATIONS) AND CHAIN HOIST BACK–UP WITH PADLOCK FOR CHAIN; LOCK CYLINDER FOR ELECTRICAL SWITCH IN HOIST. PROVIDE FULL LAP PLASTIC STRIPS. REFER TO DETAIL 2/A–1.01 FOR LOCATION OF MOTOR HOIST OPERATOR.
2. UNDERCUT DOOR 3/4"; 24" SQUARE STEEL LOUVERED VENT–18 GA. "Y" BLADE, PRIMED, TO BE PAINTED TO MATCH DOOR FRAME. FLOOR STOP (MOUNT CLOSE TO FRAME TO AVOID TRIPPING HAZARD).
3. OVERHEAD SECTIONAL GLAZED DOOR WITH MOTOR HOIST (REFER TO SPECIFICATIONS) AND CHAIN HOIST BACK–UP WITH PADLOCK; 3" HEAVY DUTY TRACK; PROVIDE 3 BUTTON REMOTE SWITCH AT FRONT WALL (REFER TO ELECTRICAL)

FINAL | SECOND | ORIGINAL

REVISIONS
◇ PRE-BID SET ISSUE DATE △ POST BID SET ISSUE DATE

DATE	DESCRIPTION
11.04.25	△1 Plan Review Comments
10.07.26	△2 Criteria Updates

STATE OF FLORIDA PERRY M. PETRILLO REGISTERED ARCHITECT AR95158

LICENSE:
NCARB No. 44,575
NEW JERSEY
Lic. No. 12119
NEW YORK
Lic. No. 094375–1
PENNSYLVANIA
Lic. No. RA–015310–B
VIRGINIA
Lic. No. 0401 011655
FLORIDA
Lic. No. AR95158

PERRY M. PETRILLO ARCHITECTS PC
9 Park Avenue
Park Ridge, New Jersey 07656
Telephone (201) 307-6153
Facsimile (201) 307-6158

LOWE'S HOME CENTERS, LLC
1000 LOWE'S BOULEVARD
MOORESVILLE, NC 28117
704.758.1000 (PH.)

THIS DRAWING IS THE PROPERTY OF LOWE'S HOME CENTERS, LLC. ANY USE OR REPRODUCTION IN WHOLE OR PART IS PROHIBITED WITHOUT THE EXPRESSED WRITTEN CONSENT OF LOWE'S HOME CENTERS, LLC. COPYRIGHT 2025-2027 ALL RIGHTS RESERVED

LOWE'S

DOOR AND HARDWARE SCHEDULE

LOWE'S OF WESTLAKE
5683 SEMINOLE PRATT WHITNEY RD.
Westlake, Florida, 33470

PCN: 77-40-43-01-29-000.0010
PROJECT No: 23.200 | DRAWN BY: LGM | CHECKED BY:

CRITERIA
ISSUE DATE: 02-2025
PERMIT SET
ISSUE DATE: 08-22-2025
CONSTRUCTION SET
ISSUE DATE: 04-14-2025
DRAWING NUMBER:

A-6.0